

Leading solution provider of IP-based video transmission

## **Deployment and Notice**

# Kiloview NDI Core Server Deployment Guide

(V2.0 version)



## CONTENTS

1	Kilo	view NDI Core server deployment	1
	1.1	Server environment preparation	1
		<ul><li>1.1.1 Hardware environment</li><li>1.1.2 Software environment</li><li>1.1.3 Network environment</li></ul>	1
	1.2	Login to server	2
	1.3	Deployment guide	3
	1.4	Login authentications	7
2	Gen	eral Questions and Solutions	8
	2.1	If there is an error message during the deployment process	8
	2.2	No response for a long time for the installation of the docker	8
	2.3	Fail to pull image	9
	2.4	NDI Core could not be logged in normally	10
	2.5	How to set static IP address for NDI Core	11





#### Note

To deploy the NDI Core, you need to load the NDI Core mirror locally. Please contact the sales staff at Kiloview or send an email to info@kiloview.com to obtain the mirror.

## **1** Kiloview NDI Core server deployment

### **1.1 Server environment preparation**

#### 1.1.1 Hardware environment

Processor: High frequency CPU, such as E2288G, 12 Generation Core i5 12600K.

Hard disk: 64G or higher.

Memory: 4GB RAM or above 16G.

Network card: one or more 10G or higher speed network card.

#### 1.1.2 Software environment

Operation system: Linux64-bit operating system (Ubuntu 18.04, 20.04) .

#### 1.1.3 Network environment

Internet application tools and image files.

LAN Bandwidth: 10 Gigabit networks.



#### 1.2 Login to server

You can use remote terminal software to login to the server, Xshell or PuTTy is recommended.

Xshell download website: https://www.netsarang.com/zh/xshell-download/

PuTTy download website: https://www.chiark.greenend.org.uk/~sgtatham/putty/latest.html

1) After installing Xshell, enter IP address of the server in the new session and use SSH protocol to

communicate. The default port is 22, click "Ok" after input completed.

Connection	Connection	
Authentication     Login Prompts     Login Scripts     SSH     SSH     Scurity     Tunneling     SFTP     TELNET     RLOGIN     SERIAL     Proxy	General Name: Protocol: Host: Port Number: Description:	server name SSH Server IP address 22
<ul> <li>Keep Alive</li> <li>Terminal</li> <li>Keyboard</li> <li>VT Modes</li> <li>Advanced</li> <li>Appearance</li> <li>Window</li> </ul>	Reconnect Reconnect au Interval: TCP Options	tomatically if connection is terminated unexpectedly          0
	Use Nagle's al	gorithm



2) Enter the user name and password in the pop-up dialog box. Ordinary users need sudo to obtain

management right or log in as root user. The deployment process in the following is completed by

root user.

You can enter "sudo su-" in command window to switch to the root user.


## 1.3 Deployment guide

Step 1: Install container. Enter "curl -fsSL https://get.docker.com | bash" in the terminal window.

root@kiloview:/# curl -fsSL https://get.docker.com   sh								
# Executing docker	# Executing docker install script, commit: 93d2499759296ac1f9c510605fef85052a2c32be							
+ sh -c apt-get up	+ sh -c apt-get update -qq >/dev/null							
+ sh -c DEBIAN_FRO	+ sh -c DEBIAN_FRONTEND=noninteractive apt-get install -y -qq apt-transport-https ca-certificates curl >/dev/null							
+ sh -c curl -fsS	+ sh -c curl -fsSL "https://download.docker.com/linux/ubuntu/gpg"   gpgdearmoryes -o /usr/share/keyrings/docker-archive-							
keyring.gpg								
+ sh -c echo "deb	<pre>s -c echo "deb [arch=amd64 signed-by=/usr/share/keyrings/docker-archive-keyring.gpg] https://download.docker.com/linux/ubuntu</pre>							
<pre>focal stable" &gt; /</pre>	etc/apt/sources.list.d/docker.list							
+ sh -c apt-get up	pdate -qq >/dev/null							
+ sh -c DEBIAN_FRO	DNTEND=noninteractive apt-get install -y -qqno-install-recommends docker-ce-cli docker-scan-plugin docker-							
ce >/dev/null								
+ version_gte 20.1	10							
+ [ -z ]								
+ return 0								
+ sh -c DEBIAN_FRO	DNTEND=noninteractive apt-get install -y -qq docker-ce-rootless-extras >/dev/null							
+ sh -c docker ver	rsion							
Client: Docker H	Engine - Community							
Version:	20.10.11							
API version:	1.41							
Go version:	go1.16.9							
Git commit:	dea9396							
Built:	Thu Nov 18 00:37:06 2021							
05/Arch:	linux/amd64							
Context:	default							
Experimental:	true							
Server: Docker Eng	gine - Community							
Engine:								
Version:	20.10.11							
API version:	1.41 (minimum version 1.12)							
Go version:	go1.16.9							
Git commit:	847da18							
Built:	Thu Nov 18 00:35:15 2021							
05/Arch:	linux/amd64							
Experimental:	false							
containerd:								
Version:	1.4.12							
GitCommit:	7b11cfaabd73bb80907dd23182b9347b4245eb5d							
runc:								
Version:	1.0.2							
GitCommit:	v1.0.2-0-g52b36a2							
docker-init:								
Version:	0.19.0							
GitCommit:	de40ad0							



#### Step 2: Install NDI discovery tool. Enter "apt install avahi-daemon" in the terminal window.




Enter Y behind "Do you want to continue?[Y/n]". Waiting for the installation completed.

Step 3: Install netdata to obtain CPU, network datasheet, etc. Enter

"docker run -d --name status --restart=always -v /var/run/docker.sock:/var/run/docker.sock:ro --pid

host --network host -e GLANCES\_OPT="-w" nicolargo/glances" in the terminal window.



Step 4: Upload NDI Core image to the server

(1) Upload NDI Core image from personal computer to server.



#### Note

NDI Core image need to be uploaded to Liunx system from NDI local personal computer,

which is required to transfer files by a file transfer tool. Deployers can use xftp files

transferring tool that comes with the Xhell or other file transfer tool, such as SecureCRT.



Step 1: Click file transfer icon in the Xhell.



Step 2: Drag NDI Core image file in your computer from left window to the right window, to finish files

transferring from local PC to server. (Please contact Kiloview sales or mail to info@kiloview.com with

NDI Core image documents).

🐻 NDI image file - Xi	ftp 7								-		×
File Edit View (	Commands T	ools Windo	w Help								
📮 🖿 - । % %	- 🔜 -	· 📄 🖻 🛛 🗸	=   🗐 📳   🌑 -   📀	0 🖗 🕜 🚍							
🔒 sftp://192.168.28.1							+ kiloview		Password		
📕 To add the curre	nt session, click	c on the left a	rrow button.								
NDI image file	×			$\prec \rightarrow$	• NDI矩阵 ×						<
← - → - 🔂 D:\ND	I image file			✓ ★ • K O	← - → - 🗋 /home/	kiloview			~	* • 🖪	
Name	Size	Type File folder	Modified		Name	Size	Туре	Modified	Attributes	Owner	
trial_ndimatrix	290.15MB		2021/11/9, 14:44								
Transfers Logs											
Name	Sta	itus Pr	ogress Size	Local Path	<-> Remote P	Path	Speed	Estimate E	lapsed		
Connected to 192.168.28.	120.22							Binary 1 Object(s	s) are selected	290.15MB	

(2) Load NDI Core image in the server

docker load -i kv\_ndicore\_pro\_011801.tar





#### Note

If the location of the NDI image file is not in the current directory, you need to specify the

folder where NDI image file is located.

For example: If the directory where NDI image file is located as /home/kiloview, then the

NDI image file loading command is

"docker load -i /home/kiloview/kv\_ndicore\_pro\_011801.tar"

	untu# docker load -i kv_ndicore_pro_011801.tar	
	[>]	
	[>]	
	[>]	15.87kB/15.87kB
	[>]	3.072kB/3.072kB
	[>]	27.69MB/27.69MB
	[======>]	114.3MB/114.3MB
	[======>]	3.584kB/3.584kB
	[>]	2.56kB/2.56kB
	[>]	2.048kB/2.048kB
	[>]	1.536kB/1.536kB
	[>]	4.643MB/4.643MB
bda72356d77c: Loading layer	[>]	9,728kB/9,728kB
	[>]	39.62MB/39.62MB
7e47cfdd3260: Loading layer	[>]	556kB/556kB
	[>]	3.072kB/3.072kB
87bf4592c061: Loading layer	[>]	36.35kB/36.35kB
8017a395ddee: Loading layer	[>]	16.38kB/16.38kB
f275a7a61f6f: Loading layer	[>]	10.46MB/10.46MB
e98830ac8618: Loading layer	[>]	14.39MB/14.39MB
al0c5d895642: Loading layer	[>]	927.7kB/927.7kB
87e801439ab8: Loading layer	[>]	9.403MB/9.403MB
1488b496f22c: Loading layer	[>]	879.6kB/879.6kB
4ee4f7e0dd9a: Loading layer	[>]	894.5kB/894.5kB
	[>]	1.386MB/1.386MB
f0af0a693169: Loading laver	[>]	891.9kB/891.9kB
	[>]	1.038MB/1.038MB
8687bcb79567: Loading laver	[>]	1.086MB/1.086MB
	[>]	2.048kB/2.048kB
	[>]	10.31MB/10.31MB
	[======================================	52.75MB/52.75MB
	[======================================	3.584kB/3.584kB
	[>]	636,9kB/636,9kB
	[======================================	242.7kB/242.7kB
Loaded image: kiloview/kv n		

#### Step 4: Run container

docker run -d -v /root/cp\_data3:/data/configs -v /etc/timezone:/etc/timezone -v

/etc/localtime:/etc/localtime -v /var/run/avahi-daemon:/var/run/avahi-daemon -v

/var/run/dbus:/var/run/dbus --restart=always --name kv\_ndicore\_senior\_011801 --network host --

privileged=true kiloview/kv\_ndicore\_senior\_011801:latest

Copyright  $\ensuremath{\mathbb{C}}$  KILOVIEW Electronics CO., LTD. All rights reserved.



3396c01c88c1: Loading layer [
Loaded image: kiloview/kv_ndicore_senior_011801:latest
root@VM-0-9-ubuntu:/home/ubuntu# docker run -d -v /root/cp_data3:/data/configs -v /etc/timezone:/etc/timezone -v
/etc/localtime:/etc/localtime -v /var/run/avahi-daemon:/var/run/avahi-daemonv /var/run/dbus:/var/run/dbusrestart=always
name kv_ndicore_senior_011801network hostprivileged=true kiloview/kv_ndicore_senior_011801;latest
db1924fe5313aa9201c2054877d61882633adfdbefe0001ac5e6642a6d6c59ba



Note:

The last image name in the above command (like kv\_ndicore\_senior\_011801 in the below picture) must be the same as the name behind the loaded image at the top of the command line.

## 1.4 Login authentications

Enter "IP address of server:81" in the browser (Google is recommended), press enter to display the

login interface of the NDI Core. The default user name and password are *admin*.

NDI Core						
admin						
{	٢					
Login						



## **2** General Questions and Solutions

## 2.1 If there is an error message during the deployment process.

Solution:

Please check the version of your operation system, currently it only supports Linux64-bit operating system

(Ubuntu 18.04+ / Debian 9+)

(1) Check linux digits: getconf LONG\_BIT

ubuntu@VM-4-5-ubuntu:~\$ getconf LONG\_BIT 64 ubuntu@VM-4-5-ubuntu:~\$

(2) Check the version number of the linux: cat /proc/version

ubuntu@VM-4-5-ubuntu:~\$ cat /proc/version							
Linux version 5.4.0-77-generic (buildd@lgw01-amd64-028)	(gcc version 9.3.0 (Ubuntu 9.3.0-17ubuntu1~20.04))						
#86-Ubuntu SMP Thu Jun 17 02:35:03 UTC 2021							
ubuntu@VM-4-5-ubuntu:~\$							

## 2.2 No response for a long time for the installation of the docker.

Solution:

The process of the installation is relatively slow, please wait patiently. You can use command "docker

version" to check and confirm whether the installation is successful.



root@ndi:~/cp_data3	
Client: Docker Engi	
Version:	20.10.6
API version:	1.41
Go version:	go1.13.15
Git commit:	370c289
Built:	Fri Apr 9 22:47:17 2021
0S/Arch:	linux/amd64
Context:	default
Experimental:	true
Server: Docker Engi	ne - Community
Engine:	
Version:	20.10.6
API version:	1.41 (minimum version 1.12)
Go version:	gol.13.15
Git commit:	8728dd2
Built:	Fri Apr 9 22:45:28 2021
0S/Arch:	linux/amd64
Experimental:	false
containerd:	
Version:	1.4.4
GitCommit:	05f951a3781f4f2c1911b05e61c160e9c30eaa8e
runc:	
Version:	1.0.0-rc93
GitCommit:	12644e614e25b05da6fd08a38ffa0cfe1903fdec
docker-init:	
Version:	0.19.0
GitCommit:	de40ad0
root@ndi:~/cp data3	#

## 2.3 Fail to pull image



Solution:

To pull the image, you need to get the image file by the internet. If the network delay is high or you

cannot connect to the internet, kindly check whether the network is smooth by ping an external website.

Copyright  $\ensuremath{\mathbb{C}}$  KILOVIEW Electronics CO., LTD. All rights reserved.



## 2.4 NDI Core could not be logged in normally

Solution:

Check the server whether it could start normally. "win+R" to open command prompt window -> "cmd"

- -> "ping server ip".
- (1) If it is able to ping the server IP, please check via below command.
  - <1>Check the status of running docker: systemctl status docker



If docker could not start normally, start docker: systemctl start docker

<2>Check the status of running container: docker ps -a

root@ndi:~/cp	data3# docker ps -a					
CONTAINER ID	IMAGE	COMMAND	CREATED	STATUS	PORTS	NAMES
563282ea0ee8	kiloview/trial_ndimatrix:latest	"/start_server.sh"	24 hours ago	Up 24 hours		trial_ndimatric
2594ce003d0d	nicolargo/glances	"/bin/sh -c 'python3…"	24 hours ago	Up 24 hours		status
root@ndi:~/cp_	data3#					

If container runs abnormally, execute below command to delete container and image, then

redeploy as deployment guide.

Stop all containers: docker stop \$(docker ps -aq)

Delete all containers: docker rm \$(docker ps -aq)

Delete all images: docker rmi \$(docker images -q)

(2) If it is unable to ping the server IP, please check as below instruction.

<1> Check whether maintenance PC and server run normally or not and whether LAN port light

flashes normally or not.

<2> The server IP maybe already changed, directly connect server "win+R" -> "cmd" ->

"ifconfig", and apply changed IP address: 81 to visit.

#### 2.5 How to set static IP address for NDI Core

Solution:

The ways of setting static IP address may be different as different operation system. Configuration ways

in below applies to ubuntu 20.04 version.

sudo vi /etc/netplan/00-installer-config.yaml



#### Note:

(1) The Internet configuration file name for different minor versions may be different,


as "00-installer-config.yaml " files name is different, enter netplan file via cd /etc/netplan, search Internet configuration file, enter corresponding Internet configuration files by vi command.

- (2) Press "i" to access the file editing mode.
- (3) After inputting, enter "ESC", and then enter" :wq ", save the file and exit.



(4) If you make a mistake input and don't want to save the file, press "ESC" and

input ":q!", exit without saving files.



## 2.6 It shows "no such file or directory" error during command

#### execution.

root@1:~# docker run -d -v /home/data:/data/configs -v /var/run/avahi-daemon:/v
ar/run/avahi-daemon -v /var/run/dbus:/var/run/dbus --restart=always --name kv\_n
dimatrix --network host --privileged=true kiloview/trial\_ndimatrix:latest
-bash: docker run -d -v /home/data:/data/configs -v /var/run/avahi-daemon:/var/
run/avahi-daemon -v /var/run/dbus:/var/run/dbus --restart=always --name kv\_ndim
atrix: No such file or directory
root@1:~# ls
snap

Solution:

When you copy the command from the file, it may include the form character and cause the

command to change. When you encounter this, please execute the command manually.



For more questions, please contact us via: https://www.kiloview.com/en/support



Please scan with browser.

#### **KILOVIEW Electronics CO., LTD.**

Tel: 86-18573192787 Email: support@kiloview.com Web: www.kiloview.com/en Address: B4-106/109, Jiahua Intelligence Valley Industrial Park, 877 Huijin Road, Yuhua District, Changsha City, Hunan Province, China.